BANGALORE DIVISION.

Dated 19th July 1905.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Sanitary Range, up to 7th August 1905 for constructing drains in the Basavangudi Extension. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's office at Public Offices between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Items.	*Quantities.*
1. Earthwork, excavation	C. yds. 1,783
2. Surki concrete	C. ft. 30,622
3. Burnt stone slabs 3" thick, dressed	S. ft. 26,098
4. Plastering with cement ½ inch thick	Sqr. 427
5. Burnt brick in surki mortar	C. ft. 2,490
6. House connections	No. 500
7. Blasting rock	C. yds. L. S.
8. Pipe-laying	R. ft. 9,260 for 6" to 12" stoneware pipes.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing drains in the Basavangudi Extension;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

K. PRAHLADA RAO, *Asst. Engr., Sanitary Range.*

SHIMOGA DIVISION.

Dated 25th July 1905.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 30th August 1905, for extending Avinahalli-Karur road from Hurle stream to the ghat head at Kogaru, Sagar Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1908.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for extending Avinahalli-Karur road from Hurle stream to the ghat head at Kogaru, Sagar Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.